

**OFFICE OF THE REGULATED MARKET COMMITTEE MALKANGIRI,**  
**MALKANGIRI, ODISHA**  
**TENDER CALL NOTICE**

NO-408/2010

Date- 13/08/10

Sealed in tenders are invited from the eligible contractors of class 'B' & 'A' Registered under W.R/R.D/P.W.D. of GOvt. of Odisha. Intending contractors may download the tender paper from the web site <http://www.malkangiri.nic.in> during **17/08/10** to **30/08/10**. The cost of Tender document as mentioned below in column no (6) is to be accompanied with tender documents in shape of Demand draft/Bankers cheque/pay orders in any nationalised bank payable at Malkangiri in favour of, secretary R.M.C. Malkangiri. The tender documents also must be accompanied with E.M.D of being 2% as mentioned below in column no (4) of tender cost in shape of Bank draft/Bankers cheque/pay order drawn in any nationalised Bank payable at Malkangiri in favour of the secretary R.M.C. Malkangiri.

In case of quoting less in respect of Tender cost has to deposit the differential amount (Between Tender cost and quoted cost) at the time of submitting the tender in shape of Bank draft or pay order drawn in any Nationalised Bank in favour of the Secretary R.M.C., Malkangiri. In case of Non-submission of differential cost at the time of submitting tenders, the tender will be treated as rejected.

The tender will be received up to 2.PM of dated **30/08/10** in the Office of The Regulated Market Committee Malkangiri through registered post/speed post of post & telegraph Deptt. and will be opened on dated **30/08/10** at 3.00 P.M in the OFFICE OF THE R.M.C, MALKANGIRI. in presence of the tenderers or their authorised agents who wishes to attend . Authorized person should have a copy of authorization letter from the concerned tenderer without which he will not be allowed to sit inside the opening hall. The undersigned is not responsible for any loss or postal delay. The terms and conditions of this tender call notice and terms and conditions supplied with tender schedule both are final and binding strictly.

The Engineer contractor shall have to furnish the required EMD as mentioned in column No.4.

### DETAILS OF THE TENDER

	Name of the Work	Approx. Tender cost.  (Rs)	EMD @ 2%  (Rs)	Class of Contractor	Tender Paper Cost (Non Refundable (in Rs.)	Time of Completion
(1)	(2)	(3)	(4)	(5)	(6)	(7)
1.	Construction of 500 MT Godown no-10 at Main Market yard RMC Malkangiri.	2270505.00	45410.00	'B' &'A'	Rs.10000.00 + 4% VAT	8 Months
2.	Construction of 500 MT Godown no-11 at Main Market yard RMC Malkangiri.	2270505.00	45410.00	'B' &'A'	Rs.10000.00 + 4% VAT	8 Months
3	Construction of 500 MT Godown no-2 at Kalimela Market yard RMC Malkangiri.	2278211.00	45570.00	'B' &'A'	Rs.10000.00 + 4% VAT	8 Months
4	Construction of 500 MT Godown no-2 at Mathily Market yard RMC Malkangiri.	2327360.00	46550.00	'B' &'A'	Rs.10000.00 + 4% VAT	8 Months
5	Construction of 500 MT Godown no-2 at Korukonda Market yard RMC Malkangiri.	2228244.00	44570.00	'B' &'A'.	Rs.10000.00 + 4% VA	8 Months

For the above work, the tenderer must have to fulfill the following conditions

A = Tenderer must be a valid. A or B class license holder with valid registration certificate of VAT/ITCC/PAN.

B = The Tenderer must have successfully completed any similar nature of minimum 500MT or above Godown work during last two financial year in any department of Govt of Odisha/Govt of Odisha undertaking. Experience and completion certificate to the said criteria must be attached with the tender documents from the Divisional head of the concerned Department.

C= The bidder has to submit an affidavit towards authenticity of his documents/ credentials.

D = The bidder has to obey each and all the clauses strictly without which the bid will be rejected then and there.

The authority is not responsibly for any omission of item of works/clauses at the time of down loading and also the Authority reserves the right to accept or reject the tender or scope of the work may be reduced or be increased without showing any reason thereof. .

-sd-

**Sealed in tender to be addressed to**

**THE SECRETARY, REGULATED MARKET  
COMMITTEE, MALKANGIRI  
AT/PO- MALKANGIRI  
DIST- MALKANGIRI (ODISHA)**

**SUB-COLLECTOR  
MALKANGIRI  
-CUM-  
CHAIRMAN, RMC.,  
MALKANGIRI**

**OFFICE OF THE REGULATED MARKET  
COMMITTEE MALKANGIRI.**

AT/PO : MALKANGIRI

DIST : MALKANGIRI

**DETAILED TENDER SCHEDULE**

**NAME OF THE WORK**

**CONSTRUCTION OF 500 MT GODOWN NO-10 AT  
MAIN MARKET YARD.**

# OFFICE OF THE REGULATED MARKET COMMITTEE

## MALKANGIRI.

AT/Po – MALKANGIRI

Dist – MALKANGIRI

### TENDER SCHEDULE

Name Of The Work : Construction of 500 MT Godown  
no-10 at Main market yard.

Tender Cost : Rs.2270505.00

Tender Paper Cost + 4% VAT : Rs. 10000.00+ 4% VAT  
(Non-refundable) (Due to download)

E.M.D @ 2% : Rs. 45410.00

Class of Contractor : 'A' & 'B'

Period of Completion : 240 Days

Date of Sale of Tender Paper :

Date & Time of receive of Tender Paper :

Date of Opening :

### OFFICIAL USE ONLY

Sold to Sri .....

Class ..... At .....

P.O. .... Via .....

Dist ..... vide M/R No .....

Date .....

*Signature of Issuing Officer*

## **TERMS AND CONDITIONS**

1. The Tenderer has to produce documents in support of his valid Regd. Licence / PAN / VAT C.C. at the time of purchase of Tender paper. Otherwise no tender papers will be issued in his favour.
2. The tender may not be the discretion of the competent authority be considered unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
3. The tenderer quoting less than the estimated cost shall have to deposit the differential amount between the estimated cost and the bidding amount (quoted cost) at the time of submitting the Tender documents in shape of Bank pay Order / Bank Draft in favour of the Secretary RMC Malkangiri failing which tender will be rejected. Any undertaking for extension of time in this regard will never be entertained.
4. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. to the labourers engaged by him in the work.
5. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

6. Items or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis approved by the competent authority or on derivation from the quoted rates.
7. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
8. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
9. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
10. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
11. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
12. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
13. The contractor is to supply necessary labour and materials, for the purpose of alignment, layout & profiling whenever required at his own cost,
14. The tenderers are required to go through each clause of P.W.D form No. F-2 carefully in addition to clauses mentioned herein before tendering for the work.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

15. Approach road to the site will be made and maintained by the contractor at his own cost and responsibility for which no payment will be made by the Department.
16. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
17. Dewatering & Cofferdamming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost & responsibility.
18. Water for execution will be arranged by the contractor at his own cost & responsibility.
19. Concrete should be vibrated with middle vibrator or pan-vibrator as per requirement at contractor's own cost.
20. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
21. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

22. Any damage caused to the work due to any cause what so ever during the execution will be made by the contractor until is handed over to the department in completed shape “Any cause” includes natural calamities of all kinds.
23. If the proportionate progress will not shown with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant panel clause of the F-2 agreement.
24. All conditions, special conditions put forth by the tenderer/contractor before or after execution of this agreement whether submitted alongwith the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement/DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
25. Over and above to this conditions the terms and conditions and rules and regulations as laid down Orissa. Detailed Standard Specifications and Orissa P.W.D. code are also binding on the part of this contract.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

**TENDER SCHEDULE FOR THE WORK:- CONSTRUCTION OF 500 MT GODOWN  
(Scientific)NO-10 MAIN MARKET YARD MALKANGIRI.**

Tender value:- Rs 2270505.00

Sl no	Item of work	Unit	Qty	Rate in Figure	Rate in words
1	Earth work excavation in foundation in hard soil with all lead and lift including dressing and levelling the bed and depositing the excavated earth at place away from work site with all lead lifts including dewatering and T&P required for the work etc complete and directed by Engineer-in-charge.	One Cum	165.91		
2	Filling foundation and plinth with sand well watered and rammed in layers with all leads and lifts etc complete as directed by Engineer-in charge.	One Cum	407.29		
3	Cement concrete (1:3:6)in foundation and floors using 4cm size hard black hand broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level,ramming,watering and curing etc complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc complete including dewatering if required.	One Cum	74.42		
4	R.R.H.G Stone masonry in cement mortar (1:6) in foundtion plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .	One Cum	92.63		

Signature of contractor.

1

Signature of chairman.

5	W.B.C.B brick masonry in cement mortar (1:6) in super structure of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .				
(i)	Up to 3 MT height.	One Cum	79.62		
(ii)	Above 3 MT height.	One Cum	78.34		
6	R C C M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hosting,lowering and laying compacting concrete in roof slab,column&beam,lintel,plinth bend, wall bond etc. icluding all RCC works with necessary slope and smooth to recive tarfelting or tresing, watering and curing ror four weeks,providing grooves or beds and fan hooks as per requirement in celling,where necessary including cost, conveyance,taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc.and including centring shuttering etc complete.				
(A)	Column base and plinth bend	One Cum	28.45		

<b>(B)</b>	Column and Beam				
<b>(i)</b>	Up to 3 MT height.	One Cum	<b>10.64</b>		
<b>(ii)</b>	Above 3 MT height.	One Cum	<b>12.32</b>		
	Lintel/chaja	One Cum	<b>8.40</b>		
<b>7</b>	Straightening bent up or coiled rods" Tor rods"cutting,bending,cracking,hooking,welding or jointing(if required) the "Tor steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc.complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Qtl	<b>60.00</b>		
<b>8</b>	Cement concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes complete in all floors.	One Cum	<b>18.76</b>		
<b>9</b>	12mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.				
<b>(i)</b>	Up to 3 MT height.	One sqm	<b>504.00</b>		

(ii)	Above 3 MT height.	One sqm	501.60		
10	16mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.	One Sqm	79.92		
10	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of of all materials,royalties,taxes and T & P etc. complete.(including cost of materials).	One Sqm	1100.00		
11	Supplying and conveyance at site MS rolling shutter of approved size as per design and angle and channels iron frame all round well finished bonds provide with locking arrangements thick fish tilled hole at the rate of 6nos per frame as may be necessary as Engineer-in -charge including cost,conveyance, taxes of all MS members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) including fitting.	One Kg	341.00		
12	Painting two coats with approved enamel paints over new iron/wood works including cost of all materials labour and T & P etc. complete as directed by Engineer-in-charge (including cost of paints primer etc).	One Sqm	168.33		
13	Carriage of excavated materials from work site to out side(within 5kms) by mechanical means as per direction of Engineer-in-charge etc.complete.	One Cum	110.60		

14	Supplying and conveyance at site M.S angle, truss, purlins of approved size as per design in all round well finished bonds provide erection, fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One Qtl	50.00		
15	Supplying and conveyance at site M.S angle with flat iron ventilator fitted with iron wire mesh in all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One KG	300.00		
16	Supply of GCI sheet of 0.40mm thick ISI mark including fixing, fitting, J-Hooks with washer, earned of materials as per direction of Engineer-in-charge including all costs of materials, GCI sheets and labour charges etc., fitting materials, taxes T & P charges etc complete.	One Sqm	526.00		
17	Supplying and conveyance at site M.S flat iron wind tie of size 50 x 6 mm all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One kg	320.00		
18	Supply, fitting, & fixing of HD bolts size 0.60m long with 15 x 15 x 4 mm base plate fixing in cement concrete (1:2:4) including all cost of materials and labour etc. complete	One kg	200.00		

19	Providing 6mm glass partition to floor base including all cost, fitting & fixing in proper level as per direction of Engineer-in-charge etc complete.	One sqm	8.00		
20	Providing antitermite treatment to the godown outer and inner side including all cost as per direction of Engineer-in-charge etc complete.	One sqm	400.00		
21	Applying tack coat using 3.00 kg of bitumen for 10 sqm and laying on the floor base of godown to prevent moisture including all cost ,convayance etc as per direction of Engineer-in-charge complete.	One sqm	300.00		
22	Supply,Installation and commisning of Fire Extinguisher ABC type Fire Extinguisher of ISI conform 5 Kg capacity make OMEX,FIRE SHELLD,CANEX including all cost convayance etc complecte.	One no	6.00		

**No of corrections -**

**No of overwrittings -**

**Junior Engineer  
O S A M BOARD**

**Asst Engineer O S A M Board  
Bhubaneswar**

**Secretary  
R M C Malkangiri**

**Chairman RMC  
Malkangiri**

**Signature of contractor**

Signature of contractor.

Signature of chairman.

**OFFICE OF THE REGULATED MARKET  
COMMITTEE MALKANGIRI.**

AT/PO : MALKANGIRI

DIST : MALKANGIRI

**DETAILED TENDER SCHEDULE**

**NAME OF THE WORK**

**CONSTRUCTION OF 500 MT GODOWN NO-11 AT  
MAIN MARKET YARD.**

# OFFICE OF THE REGULATED MARKET COMMITTEE

## MALKANGIRI.

AT/Po – MALKANGIRI

Dist – MALKANGIRI

### TENDER SCHEDULE

Name Of The Work : Construction of 500 MT Godown  
no-11 at Main market yard.

Tender Cost : Rs. 2270505.00

Tender Paper Cost + 4% VAT : Rs. 10000.00+ 4% VAT  
(Non-refundable) (Due to download)

E.M.D @ 2% : Rs. 45410.00

Class of Contractor : 'A' & 'B'

Period of Completion : 240 Days

Date of Sale of Tender Paper :

Date & Time of receive of Tender Paper :

Date of Opening :

### OFFICIAL USE ONLY

Sold to Sri .....

Class ..... At .....

P.O. .... Via .....

Dist ..... vide M/R No .....

Date .....

*Signature of Issuing Officer*

## **TERMS AND CONDITIONS**

1. The Tenderer has to produce documents in support of his valid Regd. Licence / PAN / VAT C.C. at the time of purchase of Tender paper. Otherwise no tender papers will be issued in his favour.
2. The tender may not be the discretion of the competent authority be considered unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
3. The tenderer quoting less than the estimated cost shall have to deposit the differential amount between the estimated cost and the bidding amount (quoted cost) at the time of submitting the Tender documents in shape of Bank pay Order / Bank Draft in favour of the Secretary RMC Malkangiri failing which tender will be rejected. Any undertaking for extension of time in this regard will never be entertained.
4. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. to the labourers engaged by him in the work.
5. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

6. Items or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis approved by the competent authority or on derivation from the quoted rates.
7. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
8. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
9. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
10. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
11. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
12. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
13. The contractor is to supply necessary labour and materials, for the purpose of alignment, layout & profiling whenever required at his own cost,
14. The tenderers are required to go through each clause of P.W.D form No. F-2 carefully in addition to clauses mentioned herein before tendering for the work.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

15. Approach road to the site will be made and maintained by the contractor at his own cost and responsibility for which no payment will be made by the Department.
16. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
17. Dewatering & Cofferdamming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost & responsibility.
18. Water for execution will be arranged by the contractor at his own cost & responsibility.
19. Concrete should be vibrated with middle vibrator or pan-vibrator as per requirement at contractor's own cost.
20. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
21. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

22. Any damage caused to the work due to any cause what so ever during the execution will be made by the contractor until is handed over to the department in completed shape “Any cause” includes natural calamities of all kinds.
23. If the proportionate progress will not shown with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant panel clause of the F-2 agreement.
24. All conditions, special conditions put forth by the tenderer/contractor before or after execution of this agreement whether submitted alongwith the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement/DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
25. Over and above to this conditions the terms and conditions and rules and regulations as laid down Orissa. Detailed Standard Specifications and Orissa P.W.D. code are also binding on the part of this contract.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

**TENDER SCHEDULE FOR THE WORK:- CONSTRUCTION OF 500 MT GODOWN  
(Scientific)NO-11 MAIN MARKET YARD MALKANGIRI.**

Tender value:- Rs **2270505.00**

Sl no	Item of work	Unit	Qty	Rate in Figure	Rate in words
1	Earth work excavation in foundation in hard soil with all lead and lift including dressing and levelling the bed and depositing the excavated earth at place away from work site with all lead lifts including dewatering and T&P required for the work etc complete and directed by Engineer-in-charge.	One Cum	165.91		
2	Filling foundation and plinth with sand well watered and rammed in layers with all leads and lifts etc complete as directed by Engineer-in charge.	One Cum	407.29		
3	Cement concrete (1:3:6)in foundation and floors using 4cm size hard black hand broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level,ramming,watering and curing etc complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc complete including dewatering if required.	One Cum	74.42		
4	R.R.H.G Stone masonry in cement mortar (1:6) in foundtion plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .	One Cum	92.63		

Signature of contractor.

1

Signature of chairman.

5	W.B.C.B brick masonry in cement mortar (1:6) in super structure of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .				
(i)	Up to 3 MT height.	One Cum	79.62		
(ii)	Above 3 MT height.	One Cum	78.34		
6	R C C M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hosting,lowering and laying compacting concrete in roof slab,column&beam,lintel,plinth bend, wall bond etc. icluding all RCC works with necessary slope and smooth to recive tarfelting or tresing, watering and curing ror four weeks,providing grooves or beds and fan hooks as per requirement in celling,where necessary including cost, conveyance,taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc.and including centring shuttering etc complete.				
(A)	Column base and plinth bend	One Cum	28.45		

<b>(B)</b>	Column and Beam				
<b>(i)</b>	Up to 3 MT height.	One Cum	<b>10.64</b>		
<b>(ii)</b>	Above 3 MT height.	One Cum	<b>12.32</b>		
	Lintel/chaja	One Cum	<b>8.40</b>		
<b>7</b>	Straightening bent up or coiled rods" Tor rods"cutting,bending,cracking,hooking,welding or jointing(if required) the "Tor steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc.complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Qtl	<b>60.00</b>		
<b>8</b>	Cement concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes complete in all floors.	One Cum	<b>18.76</b>		
<b>9</b>	12mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.				
<b>(i)</b>	Up to 3 MT height.	One sqm	<b>504.00</b>		

(ii)	Above 3 MT height.	One sqm	501.60		
10	16mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.	One Sqm	79.92		
10	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of of all materials,royalties,taxes and T & P etc. complete.(including cost of materials).	One Sqm	1100.00		
11	Supplying and conveyance at site MS rolling shutter of approved size as per design and angle and channels iron frame all round well finished bonds provide with locking arrangements thick fish tilled hole at the rate of 6nos per frame as may be necessary as Engineer-in -charge including cost,conveyance, taxes of all MS members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) including fitting.	One Kg	341.00		
12	Painting two coats with approved enamel paints over new iron/wood works including cost of all materials labour and T & P etc. complete as directed by Engineer-in-charge (including cost of paints primer etc).	One Sqm	168.33		
13	Carriage of excavated materials from work site to out side(within 5kms) by mechanical means as per direction of Engineer-in-charge etc.complete.	One Cum	110.60		

14	Supplying and conveyance at site M.S angle, truss, purlins of approved size as per design in all round well finished bonds provide erection, fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One Qtl	50.00		
15	Supplying and conveyance at site M.S angle with flat iron ventilator fitted with iron wire mesh in all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One KG	300.00		
16	Supply of GCI sheet of 0.40mm thick ISI mark including fixing, fitting, J-Hooks with washer, earned of materials as per direction of Engineer-in-charge including all costs of materials, GCI sheets and labour charges etc., fitting materials, taxes T & P charges etc complete.	One Sqm	526.00		
17	Supplying and conveyance at site M.S flat iron wind tie of size 50 x 6 mm all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One kg	320.00		
18	Supply, fitting, & fixing of HD bolts size 0.60m long with 15 x 15 x 4 mm base plate fixing in cement concrete (1:2:4) including all cost of materials and labour etc. complete	One kg	200.00		

19	Providing 6mm glass partition to floor base including all cost, fitting & fixing in proper levell as per direction of Engineer-in-charge etc complete.	One sqm	8.00		
20	Providing antitermite treatment to the godown outer and inner side including all cost as per direction of Engineer-in-charge etc complete.	One sqm	400.00		
21	Applying tack coat using 3.00 kg of bitumen for 10 sqm and laying on the floor base of godown to prevent moisture including all cost ,convayance etc as per direction of Engineer-in-charge complete.	One sqm	300.00		
22	Supply,Installation and commisning of Fire Extinguisher ABC type Fire Extinguisher of ISI conform 5 Kg capacity make OMEX,FIRE SHELLD,CANEX including all cost convayance etc complecte.	One no	6.00		

0.00

**No of corrections -**

**No of overwrittings -**

**Junior Engineer  
O S A M BOARD**

**Asst Engineer O S A M Board  
Bhubaneswar**

**Secretary  
R M C Malkangiri**

**Chairman RMC  
Malkangiri**

**Signiture of contractor**

Signiture of contractor.

6

Signiture of chairman.

**OFFICE OF THE REGULATED MARKET  
COMMITTEE MALKANGIRI.**

AT/PO : MALKANGIRI

DIST : MALKANGIRI

**DETAILED TENDER SCHEDULE**

**NAME OF THE WORK**

**CONSTRUCTION OF 500 MT GODOWN NO-2 AT  
KALIMELA MARKECT YARD.**

# OFFICE OF THE REGULATED MARKET COMMITTEE

## MALKANGIRI.

AT/Po – MALKANGIRI

Dist – MALKANGIRI

### TENDER SCHEDULE

Name Of The Work : Construction of 500 MT Godown  
no-2 at Kalimela market yard.

Tender Cost : Rs. 2278211.00

Tender Paper Cost + 4% VAT : Rs. 10000.00+ 4% VAT  
(Non-refundable) (Due to download)

E.M.D @ 2% : Rs. 45570.00

Class of Contractor : 'A' & 'B'

Period of Completion : 240 Days

Date of Sale of Tender Paper :

Date & Time of receive of Tender Paper :

Date of Opening :

### OFFICIAL USE ONLY

Sold to Sri .....

Class ..... At .....

P.O. .... Via .....

Dist ..... vide M/R No .....

Date .....

*Signature of Issuing Officer*

## **TERMS AND CONDITIONS**

1. The Tenderer has to produce documents in support of his valid Regd. Licence / PAN / VAT C.C. at the time of purchase of Tender paper. Otherwise no tender papers will be issued in his favour.
2. The tender may not be the discretion of the competent authority be considered unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
3. The tenderer quoting less than the estimated cost shall have to deposit the differential amount between the estimated cost and the bidding amount (quoted cost) at the time of submitting the Tender documents in shape of Bank pay Order / Bank Draft in favour of the Secretary RMC Malkangiri failing which tender will be rejected. Any undertaking for extension of time in this regard will never be entertained.
4. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. to the labourers engaged by him in the work.
5. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

**Contractor**

**chairman**  
**R.M.C. Malkangiri.**

6. Items or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis approved by the competent authority or on derivation from the quoted rates.
7. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
8. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
9. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
10. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
11. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
12. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
13. The contractor is to supply necessary labour and materials, for the purpose of alignment, layout & profiling whenever required at his own cost,
14. The tenderers are required to go through each clause of P.W.D form No. F-2 carefully in addition to clauses mentioned herein before tendering for the work.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

15. Approach road to the site will be made and maintained by the contractor at his own cost and responsibility for which no payment will be made by the Department.
16. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
17. Dewatering & Cofferdamming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost & responsibility.
18. Water for execution will be arranged by the contractor at his own cost & responsibility.
19. Concrete should be vibrated with middle vibrator or pan-vibrator as per requirement at contractor's own cost.
20. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
21. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

22. Any damage caused to the work due to any cause what so ever during the execution will be made by the contractor until is handed over to the department in completed shape “Any cause” includes natural calamities of all kinds.
23. If the proportionate progress will not shown with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant panel clause of the F-2 agreement.
24. All conditions, special conditions put forth by the tenderer/contractor before or after execution of this agreement whether submitted alongwith the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement/DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
25. Over and above to this conditions the terms and conditions and rules and regulations as laid down Orissa. Detailed Standard Specifications and Orissa P.W.D. code are also binding on the part of this contract.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

**TENDER SCHEDULE FOR THE WORK:- CONSTRUCTION OF 500 MT GODOWN  
(Scientific)NO-2 KALIMELA MARKET YARD MALKANGIRI.**

Tender value:- Rs **2278211.00**

Sl no	Item of work	Unit	Qty	Rate in Figure	Rate in words
1	Earth work excavation in foundation in hard soil with all lead and lift including dressing and levelling the bed and depositing the excavated earth at place away from work site with all lead lifts including dewatering and T&P required for the work etc complete and directed by Engineer-in-charge.	One Cum	165.91		
2	Filling foundation and plinth with sand well watered and rammed in layers with all leads and lifts etc complete as directed by Engineer-in charge.	One Cum	407.29		
3	Cement concrete (1:3:6)in foundation and floors using 4cm size hard black hand broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level,ramming,watering and curing etc complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc complete including dewatering if required.	One Cum	74.42		
4	R.R.H.G Stone masonry in cement mortar (1:6) in foundtion plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .	One Cum	92.63		

Signature of contractor.

1

Signature of chairman.

5	W.B.C.B brick masonry in cement mortar (1:6) in super structure of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .				
(i)	Up to 3 MT height.	One Cum	79.62		
(ii)	Above 3 MT height.	One Cum	78.34		
6	R C C M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hosting,lowering and laying compacting concrete in roof slab,column&beam,lintel,plinth bend, wall bond etc. icluding all RCC works with necessary slope and smooth to recive tarfelting or tresing, watering and curing ror four weeks,providing grooves or beds and fan hooks as per requirement in celling,where necessary including cost, conveyance,taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc.and including centring shuttering etc complete.				
(A)	Column base and plinth bend	One Cum	28.45		

<b>(B)</b>	Column and Beam				
<b>(i)</b>	Up to 3 MT height.	One Cum	<b>10.64</b>		
<b>(ii)</b>	Above 3 MT height.	One Cum	<b>12.32</b>		
	Lintel/chaja	One Cum	<b>8.40</b>		
<b>7</b>	Straightening bent up or coiled rods" Tor rods"cutting,bending,cracking,hooking,welding or jointing(if required) the "Tor steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc.complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Qtl	<b>60.00</b>		
<b>8</b>	Cement concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes complete in all floors.	One Cum	<b>18.76</b>		
<b>9</b>	12mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.				
<b>(i)</b>	Up to 3 MT height.	One sqm	<b>504.00</b>		

(ii)	Above 3 MT height.	One sqm	501.60		
10	16mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.	One Sqm	79.92		
10	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall inciuding all labour charges cost and conveyance of of all materials,royalties,taxes and T & P etc. complecte.(including cost of materials).	One Sqm	1100.00		
11	Supplying and conveyance at site MS rolling shutter of approved size as per design and angle and channels iron frame all round well finished bonds provide with locking arrangements thick fish tilled hole at the rate of 6nos per frame as may be necessary as Engineer-in -charge including cost,conveyance, taxes of all MS members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) including fitting.	One Kg	341.00		
12	Painting two coats with approved enamel paints over new iron/wood works including cost of all materials labour and T & P etc. complete as directed by Engineer-in-charge (including cost of paints primer etc).	One Sqm	168.33		
13	Carriage of excavated materials from work site to out side(within 5kms) by mechanical means as per direction of Engineer-in-charge etc.complete.	One Cum	110.60		

14	Supplying and conveyance at site M.S angle, truss, purlins of approved size as per design in all round well finished bonds provide erection, fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One Qtl	50.00		
15	Supplying and conveyance at site M.S angle with flat iron ventilator fitted with iron wire mesh in all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One KG	300.00		
16	Supply of GCI sheet of 0.40mm thick ISI mark including fixing, fitting, J-Hooks with washer, earned of materials as per direction of Engineer-in-charge including all costs of materials, GCI sheets and labour charges etc., fitting materials, taxes T & P charges etc complete.	One Sqm	526.00		
17	Supplying and conveyance at site M.S flat iron wind tie of size 50 x 6 mm all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One kg	320.00		
18	Supply, fitting, & fixing of HD bolts size 0.60m long with 15 x 15 x 4 mm base plate fixing in cement concrete (1:2:4) including all cost of materials and labour etc. complete	One kg	200.00		

19	Providing 6mm glass partition to floor base including all cost, fitting & fixing in proper levell as per direction of Engineer-in-charge etc complete.	One sqm	8.00		
20	Providing antitermite treatment to the godown outer and inner side including all cost as per direction of Engineer-in-charge etc complete.	One sqm	400.00		
21	Applying tack coat using 3.00 kg of bitumen for 10 sqm and laying on the floor base of godown to prevent moisture including all cost ,convayance etc as per direction of Engineer-in-charge complete.	One sqm	300.00		
22	Supply,Installation and commissoning of Fire Extinguisher ABC type Fire Extinguisher of ISI conform 5 Kg capacity make OMEX,FIRE SHELLD,CANEX including all cost convayance etc complecte.	One no	6.00		

**No of corrections -**

**No of overwrittings -**

**Junior Engineer  
O S A M BOARD**

**Asst Engineer O S A M Board  
Bhubaneswar**

**Secretary  
R M C Malkangiri**

**Chairman RMC  
Malkangiri**

**Signiture of contractor**

Signiture of contractor.

6

Signiture of chairman.

**OFFICE OF THE REGULATED MARKET  
COMMITTEE MALKANGIRI.**

AT/PO : MALKANGIRI

DIST : MALKANGIRI

**DETAILED TENDER SCHEDULE**

**NAME OF THE WORK**

**CONSTRUCTION OF 500 MT GODOWN NO-2 AT  
MATHILY MARKECT YARD.**

# OFFICE OF THE REGULATED MARKET COMMITTEE

## MALKANGIRI.

AT/Po – MALKANGIRI

Dist – MALKANGIRI

### TENDER SCHEDULE

Name Of The Work : Construction of 500 MT Godown  
no-2 at Mathily market yard.

Tender Cost : Rs. 2327360.00

Tender Paper Cost + 4% VAT : Rs. 10000.00+ 4% VAT  
(Non-refundable) (Due to download)

E.M.D @ 2% : Rs. 46550.00

Class of Contractor : 'A' & 'B'

Period of Completion : 240 Days

Date of Sale of Tender Paper :

Date & Time of receive of Tender Paper :

Date of Opening :

### OFFICIAL USE ONLY

Sold to Sri .....

Class ..... At .....

P.O. .... Via .....

Dist ..... vide M/R No .....

Date .....

*Signature of Issuing Officer*

## **TERMS AND CONDITIONS**

1. The Tenderer has to produce documents in support of his valid Regd. Licence / PAN / VAT C.C. at the time of purchase of Tender paper. Otherwise no tender papers will be issued in his favour.
2. The tender may not be the discretion of the competent authority be considered unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
3. The tenderer quoting less than the estimated cost shall have to deposit the differential amount between the estimated cost and the bidding amount (quoted cost) at the time of submitting the Tender documents in shape of Bank pay Order / Bank Draft in favour of the Secretary RMC Malkangiri failing which tender will be rejected. Any undertaking for extension of time in this regard will never be entertained.
4. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. to the labourers engaged by him in the work.
5. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

**Contractor**

**chairman**  
**R.M.C. Malkangiri.**

6. Items or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis approved by the competent authority or on derivation from the quoted rates.
7. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
8. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
9. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
10. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
11. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
12. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
13. The contractor is to supply necessary labour and materials, for the purpose of alignment, layout & profiling whenever required at his own cost,
14. The tenderers are required to go through each clause of P.W.D form No. F-2 carefully in addition to clauses mentioned herein before tendering for the work.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

15. Approach road to the site will be made and maintained by the contractor at his own cost and responsibility for which no payment will be made by the Department.
16. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
17. Dewatering & Cofferdamming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost & responsibility.
18. Water for execution will be arranged by the contractor at his own cost & responsibility.
19. Concrete should be vibrated with middle vibrator or pan-vibrator as per requirement at contractor's own cost.
20. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
21. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

22. Any damage caused to the work due to any cause what so ever during the execution will be made by the contractor until is handed over to the department in completed shape “Any cause” includes natural calamities of all kinds.
23. If the proportionate progress will not shown with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant panel clause of the F-2 agreement.
24. All conditions, special conditions put forth by the tenderer/contractor before or after execution of this agreement whether submitted alongwith the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement/DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
25. Over and above to this conditions the terms and conditions and rules and regulations as laid down Orissa. Detailed Standard Specifications and Orissa P.W.D. code are also binding on the part of this contract.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

**TENDER SCHEDULE FOR THE WORK:- CONSTRUCTION OF 500 MT GODOWN  
(Scientific) NO-2 MATHILY MARKET YARD MALKANGIRI.**

Tender value:- Rs **2327360.00**

Sl no	Item of work	Unit	Qty	Rate in Figure	Rate in words
1	Earth work excavation in foundation in hard soil with all lead and lift including dressing and levelling the bed and depositing the excavated earth at place away from work site with all lead lifts including dewatering and T&P required for the work etc complete and directed by Engineer-in-charge.	One Cum	165.91		
2	Filling foundation and plinth with sand well watered and rammed in layers with all leads and lifts etc complete as directed by Engineer-in charge.	One Cum	407.29		
3	Cement concrete (1:3:6)in foundation and floors using 4cm size hard black hand broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level,ramming,watering and curing etc complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc complete including dewatering if required.	One Cum	74.42		
4	R.R.H.G Stone masonry in cement mortar (1:6) in foundtion plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .	One Cum	92.63		

Signature of contractor.

1

Signature of chairman.

5	W.B.C.B brick masonry in cement mortar (1:6) in super structure of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .				
(i)	Up to 3 MT height.	One Cum	79.62		
(ii)	Above 3 MT height.	One Cum	78.34		
6	R C C M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hosting,lowering and laying compacting concrete in roof slab,column&beam,lintel,plinth bend, wall bond etc. icluding all RCC works with necessary slope and smooth to recive tarfelting or tresing, watering and curing ror four weeks,providing grooves or beds and fan hooks as per requirement in celling,where necessary including cost, conveyance,taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc.and including centring shuttering etc complete.				
(A)	Column base and plinth bend	One Cum	28.45		

Signature of contractor.

Signature of chairman.

<b>(B)</b>	Column and Beam				
<b>(i)</b>	Up to 3 MT height.	One Cum	<b>10.64</b>		
<b>(ii)</b>	Above 3 MT height.	One Cum	<b>12.32</b>		
	Lintel/chaja	One Cum	<b>8.40</b>		
<b>7</b>	Straightening bent up or coiled rods" Tor rods"cutting,bending,cracking,hooking,welding or jointing(if required) the "Tor steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc.complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Qtl	<b>60.00</b>		
<b>8</b>	Cement concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes complete in all floors.	One Cum	<b>18.76</b>		
<b>9</b>	12mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.				

(i)	Up to 3 MT height.	One sqm	504.00		
(ii)	Above 3 MT height.	One sqm	501.60		
10	16mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.	One Sqm	79.92		
10	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of of all materials,royalties,taxes and T & P etc. complecte.(including cost of materials).	One Sqm	1100.00		
11	Supplying and conveyance at site MS rolling shutter of approved size as per design and angle and channels iron frame all round well finished bonds provide with locking arrangements thick fish tilled hole at the rate of 6nos per frame as may be necessary as Engineer-in -charge including cost,conveyance, taxes of all MS members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) including fitting.	One Kg	341.00		
12	Painting two coats with approved enamel paints over new iron/wood works including cost of all materials labour and T & P etc. complete as directed by Engineer-in-charge (including cost of paints primer etc).	One Sqm	168.33		
13	Carriage of excavated materials from work site to out side(within 5kms) by mechanical means as per direction of Engineer-in-charge etc.complete.	One Cum	110.60		

Signature of contractor.

Signature of chairman.

14	Supplying and conveyance at site M.S angle, truss, purlins of approved size as per design in all round well finished bonds provide erection, fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One Qtl	50.00		
15	Supplying and conveyance at site M.S angle with flat iron ventilator fitted with iron wire mesh in all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One KG	300.00		
16	Supply of GCI sheet of 0.40mm thick ISI mark including fixing, fitting, J-Hooks with washer, earned of materials as per direction of Engineer-in-charge including all costs of materials, GCI sheets and labour charges etc., fitting materials, taxes T & P charges etc complete.	One Sqm	526.00		
17	Supplying and conveyance at site M.S flat iron wind tie of size 50 x 6 mm all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One kg	320.00		
18	Supply, fitting, & fixing of HD bolts size 0.60m long with 15 x 15 x 4 mm base plate fixing in cement concrete (1:2:4) including all cost of materials and labour etc. complete	One kg	200.00		

<b>19</b>	Providing 6mm glass partition to floor base including all cost, fitting & fixing in proper levell as per direction of Engineer-in-charge etc complete.	<b>One sqm</b>	<b>8.00</b>		
<b>20</b>	Providing antitermite treatment to the godown outer and inner side including all cost as per direction of Engineer-in-charge etc complete.	<b>One sqm</b>	<b>400.00</b>		
<b>21</b>	Applying tack coat using 3.00 kg of bitumen for 10 sqm and laying on the floor base of godown to prevent moisture including all cost ,convayance etc as per direction of Engineer-in-charge complete.	<b>One sqm</b>	<b>300.00</b>		
<b>22</b>	Supply,Installation and commisoning of Fire Extinguisher ABC type Fire Extinguisher of ISI conform 5 Kg capacity make OMEX,FIRE SHELLD,CANEX including all cost convayance etc complecte.	<b>One no</b>	<b>6.00</b>		

**No of corrections -**

**No of overwrittings -**

**Junior Engineer  
O S A M BOARD**

**Asst Engineer O S A M Board  
Bhubaneswar**

**Secretary  
R M C Malkangiri**

**Chairman RMC  
Malkangiri**

**Signiture of contractor**

Signiture of contractor.

Signiture of chairman.

**OFFICE OF THE REGULATED MARKET  
COMMITTEE MALKANGIRI.**

AT/PO : MALKANGIRI

DIST : MALKANGIRI

**DETAILED TENDER SCHEDULE**

**NAME OF THE WORK**

**CONSTRUCTION OF 500 MT GODOWN NO-2 AT  
KORUKONDA MARKET YARD.**

# OFFICE OF THE REGULATED MARKET COMMITTEE

## MALKANGIRI.

AT/Po – MALKANGIRI

Dist – MALKANGIRI

### TENDER SCHEDULE

Name Of The Work : Construction of 500 MT Godown  
no-2 at Korukonda market yard.

Tender Cost : Rs. 2228244.00

Tender Paper Cost + 4% VAT : Rs. 10000.00+ 4% VAT  
(Non-refundable) (Due to download)

E.M.D @ 2% : Rs. 44570.00

Class of Contractor : 'A' & 'B'

Period of Completion : 240 Days

Date of Sale of Tender Paper :

Date & Time of receive of Tender Paper :

Date of Opening :

### OFFICIAL USE ONLY

Sold to Sri .....

Class ..... At .....

P.O. .... Via .....

Dist ..... vide M/R No .....

Date .....

*Signature of Issuing Officer*

## **TERMS AND CONDITIONS**

1. The Tenderer has to produce documents in support of his valid Regd. Licence / PAN / VAT C.C. at the time of purchase of Tender paper. Otherwise no tender papers will be issued in his favour.
2. The tender may not be the discretion of the competent authority be considered unless accompanied by attested copies of VAT C.C., Income Tax clearance certificate / PAN requisite EMD and valid registration certificate.
3. The tenderer quoting less than the estimated cost shall have to deposit the differential amount between the estimated cost and the bidding amount (quoted cost) at the time of submitting the Tender documents in shape of Bank pay Order / Bank Draft in favour of the Secretary RMC Malkangiri failing which tender will be rejected. Any undertaking for extension of time in this regard will never be entertained.
4. The contractor should abide by the fair wages clause introduced by Govt. and shall not pay dues less than the fair wages fixed by the Govt. to the labourers engaged by him in the work.
5. The right is reserved to make such increase or decrease in quantities of items of work mentioned in the schedule attached to the tender notice as may be considered necessary for satisfactory completion of the contract work and such increase or decrease shall not be entitled to any compensation and this account except extension of time where considered necessary. Right is also reserved to omit any items of works included in the tender schedule as is considered necessary and the contractor shall not be entitled to any compensation on this account.

**Contractor**

**chairman**  
**R.M.C. Malkangiri.**

6. Items or work not covered in the tender schedule shall be paid at current schedule of rates and those not covered in the said schedule of rates will be paid on actual analysis approved by the competent authority or on derivation from the quoted rates.
7. On no account the contract work should be sublet to any body without prior approval of the competent authority of the department and in such an event the contract may be rescinded.
8. No compensation for any damage done by rains or by similar action during the execution of work will be paid.
9. The contractor shall make at his own cost housing accommodation and medical aid to the labourers engaged in the work.
10. The contractor shall make arrangement at his own cost at the work site for proper storage of the materials made over to him.
11. The tender, which is not in the prescribed proforma & not strictly according to the terms and conditions of the tender call notice and specification, is liable for rejection.
12. As regards extra items of work besides the schedule of quantities written order must be obtained from the Engineer-in-charge before the work is taken up.
13. The contractor is to supply necessary labour and materials, for the purpose of alignment, layout & profiling whenever required at his own cost,
14. The tenderers are required to go through each clause of P.W.D form No. F-2 carefully in addition to clauses mentioned herein before tendering for the work.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

15. Approach road to the site will be made and maintained by the contractor at his own cost and responsibility for which no payment will be made by the Department.
16. All the materials required for bonafide use in the work, depending on the description of the departmental authority will be supplied by the contractor only. The materials will be carried to site of work by the contractor at his own cost. Before procuring the materials, the contractor should take clearance from the Engineer-in-charge and the materials produced by him should be got approved by the Engineer-in-charge before use. No departmental materials will be issued to the contractor.
17. Dewatering & Cofferdamming and diversion arrangement for drain water & road if required during execution will be done by the contractor at his own cost & responsibility.
18. Water for execution will be arranged by the contractor at his own cost & responsibility.
19. Concrete should be vibrated with middle vibrator or pan-vibrator as per requirement at contractor's own cost.
20. The contractor is entitled to pay only at the rates quoted by him and enter in the agreement. If the contractor is required to do any ancillary work for doing the main work as per the contract, it will be entirely to his account and nothing extra over and above the agreement rates will be paid.
21. The contractor will make his own arrangements to watch the materials at site at his own cost till the work is finally closed and handed over.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

22. Any damage caused to the work due to any cause what so ever during the execution will be made by the contractor until is handed over to the department in completed shape “Any cause” includes natural calamities of all kinds.
23. If the proportionate progress will not shown with 15 days from the date of commencement of the work, the contract is liable to be closed as per relevant panel clause of the F-2 agreement.
24. All conditions, special conditions put forth by the tenderer/contractor before or after execution of this agreement whether submitted alongwith the tender or before or after shall automatically stand rejected and superseded by the terms and conditions of this agreement/DTCN. The terms and conditions of the DTCN shall form part of the agreement. In case of any conflict, the terms of agreement and DTCN will prevail.
25. Over and above to this conditions the terms and conditions and rules and regulations as laid down Orissa. Detailed Standard Specifications and Orissa P.W.D. code are also binding on the part of this contract.

**Contractor**

***chairman***  
**R.M.C. Malkangiri.**

**TENDER SCHEDULE FOR THE WORK:- CONSTRUCTION OF 500 MT GODOWN  
(Scientific) NO-2 KORUKONDA MARKET YARD MALKANGIRI.**

Tender value:- Rs **2228244.00**

Sl no	Item of work	Unit	Qty	Rate in Figure	Rate in words
1	Earth work excavation in foundation in hard soil with all lead and lift including dressing and levelling the bed and depositing the excavated earth at place away from work site with all lead lifts including dewatering and T&P required for the work etc complete and directed by Engineer-in-charge.	One Cum	165.91		
2	Filling foundation and plinth with sand well watered and rammed in layers with all leads and lifts etc complete as directed by Engineer-in charge.	One Cum	407.29		
3	Cement concrete (1:3:6)in foundation and floors using 4cm size hard black hand broken granite metal of approved quality from approved quarry including hoisting, lowering and laying concrete layers not exceeding 15cm thick to the required level,ramming,watering and curing etc complete including cost and conveyance of all materials with all taxes and royalties and labour with T & P required for the work etc complete including dewatering if required.	One Cum	74.42		
4	R.R.H.G Stone masonry in cement mortar (1:6) in foundtion plinth of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .	One Cum	92.63		

Signature of contractor.

Signature of chairman.

5	W.B.C.B brick masonry in cement mortar (1:6) in super structure of approved size and quality splays cutting circular moulding and similar such type of work with necessary projection, chamfering and corbelling,watering and curing etc. complete including cost and conveyance of all materials with all taxes and royalty and all labour with T & P for the work etc complete .				
(i)	Up to 3 MT height.	One Cum	79.62		
(ii)	Above 3 MT height.	One Cum	78.34		
6	R C C M-20 using 20mm and 10mm size hard black crusher broken granite chips of approved quarry including hosting,lowering and laying compacting concrete in roof slab,column&beam,lintel,plinth bend, wall bond etc. icluding all RCC works with necessary slope and smooth to recive tarfelting or tresing, watering and curing ror four weeks,providing grooves or beds and fan hooks as per requirement in celling,where necessary including cost, conveyance,taxes and royalty of all materials and labour with T & P required for the work etc. complete in all respect but excluding cost of Tor steel and binding wires of 18 to 20 gauge and labour charges for straightening bending etc.and including centring shuttering etc complete.				
(A)	Column base and plinth bend	One Cum	28.45		

Signiture of contractor.

Signiture of chairman.

<b>(B)</b>	Column and Beam				
<b>(i)</b>	Up to 3 MT height.	One Cum	<b>10.64</b>		
<b>(ii)</b>	Above 3 MT height.	One Cum	<b>12.32</b>		
	Lintel/chaja	One Cum	<b>8.40</b>		
<b>7</b>	Straightening bent up or coiled rods" Tor rods"cutting,bending,cracking,hooking,welding or jointing(if required) the "Tor steels rods" & binding wire and tying the grills hoisting laying and placing in proper position as required for RCC works for providing if an hooks including cost, conveyance and taxes of Tor steel and binding wire of 18 to 20 gauge and labour with T & P required for the work etc.complete in all respect in all floors (weight of the binding wire will not be considered for payment) complete.	Qtl	<b>60.00</b>		
<b>8</b>	Cement concrete (1:2:4) using 12mm size hard black granite crusher broken chips with cost and conveyance of all materials and labour with T & P required for the work with royalties, taxes complete in all floors.	One Cum	<b>18.76</b>		
<b>9</b>	12mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.				
<b>(i)</b>	Up to 3 MT height.	One sqm	<b>504.00</b>		

Signature of contractor.

Signature of chairman.

(ii)	Above 3 MT height.	One sqm	501.60		
10	16mm thick cement plaster with cement mortar (1:6) to brick masonry after ranking out joint to finished smooth watering and conveyance off all materials and labour with T & P required for the work with all taxes royalty etc. complete.	One Sqm	79.92		
10	Colour washing two coats with approved cement paint over one coat of cement wash over surface of the wall including all labour charges cost and conveyance of of all materials,royalties,taxes and T & P etc. complete.(including cost of materials).	One Sqm	1100.00		
11	Supplying and conveyance at site MS rolling shutter of approved size as per design and angle and channels iron frame all round well finished bonds provide with locking arrangements thick fish tilled hole at the rate of 6nos per frame as may be necessary as Engineer-in -charge including cost,conveyance, taxes of all MS members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) including fitting.	One Kg	341.00		
12	Painting two coats with approved enamel paints over new iron/wood works including cost of all materials labour and T & P etc. complete as directed by Engineer-in-charge (including cost of paints primer etc).	One Sqm	168.33		
13	Carriage of excavated materials from work site to out side(within 5kms) by mechanical means as per direction of Engineer-in-charge etc.complete.	One Cum	110.60		

Signature of contractor.

Signature of chairman.

14	Supplying and conveyance at site M.S angle, truss, purlins of approved size as per design in all round well finished bonds provide erection, fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One Qtl	50.00		
15	Supplying and conveyance at site M.S angle with flat iron ventilator fitted with iron wire mesh in all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One KG	300.00		
16	Supply of GCI sheet of 0.40mm thick ISI mark including fixing, fitting, J-Hooks with washer, earned of materials as per direction of Engineer-in-charge including all costs of materials, GCI sheets and labour charges etc., fitting materials, taxes T & P charges etc complete.	One Sqm	526.00		
17	Supplying and conveyance at site M.S flat iron wind tie of size 50 x 6 mm all round well finished fitting and fixing as directed by Engineer-in-charge including cost, conveyance, taxes of all M S members and labour for welding etc. and fixing complete materials used in the work shall confirm to relevant I.S. specification (fitting to be done after weighment & approved by the Secretary R M C ) .	One kg	320.00		
18	Supply, fitting, & fixing of HD bolts size 0.60m long with 15 x 15 x 4 mm base plate fixing in cement concrete (1:2:4) including all cost of materials and labour etc. complete	One kg	200.00		

Signature of contractor.

Signature of chairman.

19	Providing 6mm glass partition to floor base including all cost, fitting & fixing in proper level as per direction of Engineer-in-charge etc complete.	One sqm	8.00		
20	Providing antitermite treatment to the godown outer and inner side including all cost as per direction of Engineer-in-charge etc complete.	One sqm	400.00		
21	Applying tack coat using 3.00 kg of bitumen for 10 sqm and laying on the floor base of godown to prevent moisture including all cost ,convayance etc as per direction of Engineer-in-charge complete.	One sqm	300.00		
22	Supply,Installation and commisning of Fire Extinguisher ABC type Fire Extinguisher of ISI conform 5 Kg capacity make OMEX,FIRE SHELLD,CANEX including all cost convayance etc complecte.	One no	6.00		

**No of corrections -**

**No of overwritings -**

**Junior Engineer  
O S A M BOARD**

**Asst Engineer O S A M Board  
Bhubaneswar**

**Secretary  
R M C Malkangiri**

**Chairman RMC  
Malkangiri**

**Signature of contractor**

Signature of contractor.

Signature of chairman.